

BRUHAT BENGALURU MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of the Work: Improvements to Roads and Drains at Maruthi Layout, Vinayakanagara, Seenappa Garden and Surrounding areas in Ward No. 15 (Kuvempunagara).

Sl. No.	Quantity.	Description	Unit	Rates Quotation by Sri U. Ramesh	
				In Figures	In Words
1	585.95	Earth work Excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work.	Cum	214.80	Rupees Two Hundred Fourteen And Paise Eighty Only
2	88.46	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	6414.25	Rupees Six Thousand Four Hundred Fourteen And Paise Twenty Five Only


Signature of the Contractor


Executive Engineer
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ

Sl. No.	Quantity.	Description	Unit	Rates Quotation by Sri U. Ramesh	
				In Figures	In Words
3	217.46	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately)	Cum	7237.00	Rupees Seven Thousand Two Hundred Thirty Seven Only
4	13.42	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications.	Tonne	106446.21	Rupees One Lakh(s) Six Thousand Four Hundred Forty Six And Paise Twenty One Only
5	8.22	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate)	Cum	6615.20	Rupees Six Thousand Six Hundred Fifteen And Paise Twenty Only
6	342.14	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 100 mm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete.	Sqm	2175.39	Rupees Two Thousand One Hundred Seventy Five And Paise Thirty Nine Only
7	36.00	Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 230 mm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete.	Sqm	5288.34	Rupees Five Thousand Two Hundred Eighty Eight And Paise Thirty Four Only
8	5.10	Qty above 125%	Sqm	5287.84	Rupees Five Thousand Two Hundred Eighty Seven And Paise Eighty Four Only


Signature of the Contractor

